

RTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.


Corner Code No. L-21

Note: Monument marked as shown below

History of original corner establishment:

Most recent approved GLO record, by Currin and Noland, under Special Contract dated May 4, 1887 states:

To old 1/4 sec. cor. which I re-established with a stone 18x10x8 ins. 12 ins. in the ground marked 1/4 on W. face, dug pits 18x12 ins. N. and S. from the stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high 3 1/2 ft. base over it.



Corner No. Compass Declination: 18.0°

Description of corner evidence found:

After surveying to the N.E. and re-established S.E. corners of Section 14, I re-establish this corner at the intersection of the Westerly projection of an East-West fence and the Southerly projection of a line fence to the North. The re-established corner position falls in a North-South dirt road.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" x 30" galv. iron pipe 42" in ground under the road from which:

- A 5/8" x 30" iron pin bears N 45 1/2°W - 26.86'.
A 5/8" x 30" iron pin bears N 43°E - 25.85'.
A 5/8" x 30" iron pin bears S 42°E - 28.07'.
A 5/8" x 30" iron pin bears S 51°W - 23.29'.

Each pin is capped with a yellow plastic cap marked "W.R WELLS, PLS 1106". Set a steel fence post with Bearing Object signs attached set by each pin.

Set a steel fence post 4.5' West of monument and attached a Witness Corner sign.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by .....
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71)

Umatilla County Surveyor

Date 8-92

Rec'd By KR

No. 92-92-C