

RTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. L-25

Note: Monument marked as shown below


History of original corner establishment:

Most recent approved GLO record, by L.E. Wilkes, U.S. Surveyor, under special instructions dated February 20, 1917 states:

Wilkes, in retracing the range line bet. Tps. 2 N., Rgs. 32 and 33 E., found 1/4 cor. on E. bdy. of sec. 13, which is a basalt stone, 12x8x4 ins., 18 ins. in the ground, marked 1/4 on W. face. 45 1/2 lks. W. of this corner

Set an iron post, 3 ft. long, 2 ins. dia., 26 ins. in the ground, for witness cor. to the 1/4 cor. of sec. 13 only, with brass cap marked

1/4
S13 | WC
1917



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

None. After diligent search, this corner was re-established by single proportion measurement (irregular boundary method), between the recovered N.E. corner of Section 12 and the recovered S 1/16th corner of Section 18, T2N., R33E., W.M..

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 30" x 1 1/4" iron pipe 30" in ground and mounded with earth, from which:

A brass washer bears N 30°W - 61.03', and is nailed with an alum. nail to gate post.

A brass washer bears N 61 1/2°E - 92.29', and is nailed with an alum. nail to PP&L pole.

A 5/8" x 30" iron pin bears S 59°53'E - 50.06', and is capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106". Set steel fence post near and attached a Bearing Object sign.

A brass washer bears N 86 1/2°W - 26.73', and is nailed with an alum. nail to pole no. 138561.

Brass washers are stamped "W.R. WELLS, PLS 1106", and Bearing Object signs are nailed above each washer.

Set steel fence post 3' East of monument and attached Witness Corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 8-92

Rec'd By JK

No. 92-92-C