

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.


Corner Code No. L-5

Note: Monument marked as shown below

History of original corner establishment:

Most recent approved GLO record, by Daniel Chaplin, under Contract No. 107 dated Sept. 21 1884, states:

"Set post for 1/4 Sec. corner in mound of Earth with charred stake pits & as per instructions".



Corner No. Compass Declination: 18.0°

Description of corner evidence found:

None. Corner area has been disturbed by years of farming. There appears to be the remains of an old field line South of the re-established corner point.

Re-established corner by single proportion measurement between the Northeast and Southeast corners of Section 18, using the Chaplin Record.

Description of monument and accessories established to perpetuate the original location of this corner:

Buried a 2 1/2" brass cap on a 1 1/4" x 24" flared galv. iron pipe with top of cap buried 18" below the seeded Conservation Reserve Program field.

There are no references available nearby.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by ..... (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY Umatilla County Surveyor Date 8-92 Rec'd By KR No. 92-92-C