

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. N-11

Note: Monument marked as shown below

History of original corner establishment:


Most recent approved GLO record, by Currin and Noland, under Special Contract dated May 4, 1887 states:

"Set stone 9x8x7 ins. 6 ins. in the ground for 1/4 Sec. Cor. marked 1/4 on N. face. dug pits 18x12 ins. E. & W. from stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high 3 1/2 ft. base".

In 1970, an iron pipe, which had been used in area surveys many for years, was recovered and re-monumented by James Chaffee, City Engineer, Survey No. G-1040.

Corner designation: T2N R32E

1/4 S16
S21



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

A 2 inch brass cap set in concrete, flush with the ground, alongside the South edge of an 8"x 8" railroad tie fence post. There is an East - West fence with a short run of fence to the South. There is an old illegible 'Monument' sign attached to the post.

Description of monument and accessories established to perpetuate the original location of this corner:

From the existing monument:

- A 5/8"x30" iron pin bears N 35°W - 20.43', capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".
- A 5/8"x30" iron pin bears N 44 1/2°E - 19.00', capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".
- A 5/8"x30" iron pin bears S 08°E - 15.10', capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".
- A 5/8"x30" iron pin bears S 75°W - 18.50', capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106".

Set a 5.5 foot steel fence post, on rough line, approximately 1 foot from each pin, with a Bearing Object information sign attached.

Set a steel fence post 3.0 feet South of monument and attached a Witness Corner sign.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of..... State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19..... by..... (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 8-92

Rec'd By KR

No. 92-92-C