

RTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.


Corner Code No. N-21

Note: Monument marked as shown below

History of original corner establishment:

Most recent approved GLO record, by Currin and Noland, under Special Contract dated May 4, 1887 states:

"To a point 23 lks. W. of old cor. to secs. 13 - 14 - 23 & 24. Re-established old cor. Set stone 18x12x6 ins, 12 ins. in the ground marked with 3 notches on S. and 1 on E. edges. Dug pits 18x12 ins. in each Sec. 5 1/2 ft. dist. and raised a mound of earth 2 ft. high 4 1/2 ft. base over it".



Corner No. Compass Declination: 18.0°

Description of corner evidence found:

None. This corner area has been disturbed by a deep North-South road cut. Re-established corner by double proportion measurement between found or re-established 1/4 section corners 1/2 mile North, South, East and West, using GLO Plat Record for the Currin and Noland Surveys.

Description of monument and accessories established to perpetuate the original location of this corner:

At a point N 90°00'00"W 7.03 feet from the true corner point, set a witness corner monument in the basalt roadbed. Set a 2 1/2" brass cap on a 1 1/4" O.D. by 4" galv. iron pipe in concrete 12" below the road from which:

- A 5/8" x 30" iron pin bears N 56°W - 17.0'.
- A 5/8" x 30" iron pin bears N 61°E - 21.8'.
- A 5/8" x 30" iron pin bears S 45°E - 25.7'.
- A 5/8" x 30" iron pin bears S 50 1/2°W - 18.3'.

Each pin is capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106", and a steel fence post with Bearing Object signs attached set by each pin. The iron pins reference the witness corner monument.

Set a steel fence post 8' East of monument and attached a Witness Corner sign.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by (DEPUTY)

(COUNTY OFFICIAL)

RECEIVED BY

Umatilla County Surveyor

Date 8-92

Rec'd By KF

No. 92-92-C