

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


Center line S.E. 6th and Isaac Ave.  
(Res. Add. Int. Mon. #6)

City Mon. #107

**History of original corner establishment:**

Stone set as Res. Add. Int. MON #6 and center line intersection  
by Peter Zahner in 1883.

Stone was destroyed by past construction and was found lying  
on the surface in 1970.



**Description of corner evidence found:**

NOTE

**Description of monument and accessories I established to perpetuate the  
original location of this corner**

An Electronic Distance Traverse was made from Res. B'dy MON #9 at South  
Main, down Main to Isaac, then East along S.E. Isaac to S.E. 6th, then South  
to Res. B'dy Mon #10. An AZIMUTH tie was made to Res. Add. Int. MON #7 to  
use for center line of S.E. Isaac. The distance between MON #9 and MON #10  
was found to agree with the plat distance and the traverse was adjusted.  
From the traverse point at S.E. 6th and Isaac the position for the center  
line was set, referenced, and a City of Pendleton brass cap was set. The  
brass cap is stamped " S.E. Isaac-6th" and punched for position. The monument  
is inside a valve box. All angles were turned by a one second Theodolite and  
a copy of control survey has been filed with the County surveyor.

SUBMITTED BY CITY ENGINEERING DEPT.  
Pendleton, Oregon



*James L. Chaffee*  
City Engineer

Office of ..... County of .....  
State of ....., I hereby certify that the within instrument was filed in this office  
for record on the ..... day of ....., 19....., at ..... o'clock .....m., (signed)  
..... by ..... (DEPUTY)  
(COUNTY OFFICIAL)