

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. P-13

Note: Monument marked as shown below


History of original corner establishment:

The corner was originally established by Daniel Chaplin, under Contract No. 107, dated September 21, 1864. Set post in mound of earth with charred stake, pits, and etc., as per instructions.

The corner was reset by Zenas F. Moody, under Contract No. 165, dated October 4, 1871. Set post and made mound for corner.

The corner was reset by Jas. P. Durrin and Jas. Noland, under special contract, dated May 4, 1887. Set a stone 9" x 8" x 7" with 1/4 marked on the West face, 6 inches in the ground. Dug pits North and South and raised a mound of earth.

The corner was monumented by Ralph Thompson, as indicated on Map No. H-220-Ax, in 1973. Set a brass cap after finding 6" x 7" x 14" stone marked "1/4".



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

2 1/2" brass cap on a 1 1/4" galv. iron pipe, protruding 3 inches from ground. Cap was set by Ralph Thompson, in May 1973, as referred to in map No. H-220-Ax.

This monument is located at a fence corner with fences running North and West.

Description of monument and accessories I established to perpetuate the original location of this corner:

Attached a Witness corner sign to the railroad tie fence corner post.

New bearing objects:

A 5/8" x 30" iron pin bears N 01° W - 64.8 feet. (Flush with ground).

A brass washer on West face of power pole, 1 foot above ground bears N 69° E - 136.3 feet.

A brass washer on West face of power pole, 1 foot above ground bears S 66 1/2° E - 136.3 feet.

A 5/8" x 30" iron pin bears N 87 1/2° W - 32.7 feet. (Flush with ground).

All iron pins are capped with a 1 1/2" yellow plastic cap marked: "WR WELLS, PLS 1106". Bearing object signs are wired to each pin.

Brass washers, stamped "PLS 1106", are nailed to the power poles, and have Bearing Object signs attached above the washers.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*EXPIRES 12/31/94*

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by ..... (DEPUTY)

(COUNTY OFFICIAL)