

ERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E . . , W.M.


Corner Code No. P-21

Note: Monument marked as shown below

History of original corner establishment:

The most recent approved GLO record, by Currin and Noland, under Special Contract dated May 4, 1887 states:

Found 1/4 Sec. Cor., a stone 18 X 12 X 6, firmly set in the ground marked 1/4 on W. face with pits N & S 5 1/2 ft. dist., partly filled, md. about stone almost gone.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

An ancient East-West, North-South fence intersection. After confirming this location by survey measurement, I accept the fence corner as the best remaining evidence of the location of the 1/4 corner. A search around the fence intersection did not recover the original corner stone.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" by 30" galv. iron pipe 28" in ground and surrounded with a mound of earth and stone. Set a steel fence post 3 feet West of corner with "Witness Post" sign attached.

- A 5/8" by 30" iron pin bears S01 1/2° E - 18.60 feet dist. with a yellow plastic cap marked "W.R. Wells, PLS 1106" attached.
- A 5/8" by 30" iron pin bears N88° W - 25.00 feet dist. with a yellow plastic cap marked "W.R. Wells, PLS 1106" attached.
- A 5/8" by 30" iron pin bears N00° W - 50.00 feet dist. with a yellow plastic cap marked "W.R. Wells, PLS 1106" attached.
- A 5/8" by 30" iron pin bears N87° 1/2 E - 22.00 feet dist. with a yellow plastic cap marked "W.R. Wells, PLS 1106" attached.

Set a 5.5 foot steel fence post, on rough line, approximately 1 foot from each rebar, with a Bearing Object information sign attached.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by (DEPUTY)
(COUNTY OFFICIAL)

RECEIVED BY

Umatilla County Surveyor
Date 8-92
Rec'd By KK
No. 92-92-C