

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. P-9

Note: Monument marked as shown below


History of original corner establishment:

The corner was originally established by Daniel Chaplin, under Contract No. 107, dated September 21, 1864. Set post and charred stake, in mound of earth with pits and etc., as per instructions.

The corner was reset by Zenas F. Moody, under Contract No. 165, dated October 4, 1871. Set post and made mound of earth for the corner.

The corner was reset by Jas. P. Currin and Jas. Noland, under special contract, dated May 4, 1887. Set 9" x 8" x 7" stone, 6 inches in the ground, marked 1/4 on the North face, dug pits North and South of corner, raised mound of earth alongside.

The corner was re-established by single proportionate measure, as indicated by Map No. S-94-A.



Corner No.

Compass Declination: 18.0°

Description of corner evidence found:

Found 3/4" i.d. iron pipe set by J. Val Toronto, referenced on Map No. S-94-A.

Also referenced by William R. Wells, dated 3/9/84. Map No. 84-42-B.

Description of monument and accessories established to perpetuate the original location of this corner:

At position of found 3/4" iron pipe:

Set a 2 1/2" brass cap on a 1 1/4" x 30" galv. iron pipe, 29" in the ground, with the old pipe buried along the North side of the new monument.

Set a steel fence post 3.5 feet South of the monument with Witness corner sign attached.

New Bearing Objects:

A brass washer nailed to Power Pole 36-3-B bears N 4 1/2° E - 28.7 feet. (1 foot up from ground).

A 5/8" x 30" iron pin bears S 35° E - 21.1 feet. (Flush with ground).

A 5/8" x 30" iron pin bears S 45° W - 17.6 feet. (Flush with ground).

A 5/8" x 30" iron pin bears N 81° W - 26.6 feet. (Flush with ground).

All iron pins are capped with 1 1/2" yellow plastic caps marked: " WR WELLS, PLS 1106". Bearing Object signs are wired to each iron pin.

A Bearing Object sign is nailed above the brass washer on the power pole.

REGISTERED

PROFESSIONAL

LAND SURVEYOR

William R. Wells

OREGON

JULY 22, 1977

WILLIAM R. WELLS

1106

EXPIRES 12/31/94

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by (DEPUTY)

(COUNTY OFFICIAL)

(DEPUTY)