

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 32E., W.M.

Corner Code No. R-11


Note: Monument marked as shown below

History of original corner establishment:

The corner was originally established by Daniel Chaplin, under Contract No. 107, dated September 21, 1864. Set post and charred stake in mound of earth, pits and etc., as per instructions.

The corner was reset by I.F. Moody, under Contract No. 165, dated October 4, 1871. Moody set a post and made an earth mound for the corner.

The corner was re-established by Currin and Noland, under Special Contract dated May 4, 1887. A 9" x 8" x 7" stone was set 6" in the ground, marked 1/4" on the North face, with pits dug East and West of the corner and a mound of earth raised around it.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

No evidence of the corner found. Corner was re-established by single proportion measurement between the Southwest and Southeast corners of Section 21.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" x 30" galv. iron pipe, 30" in the ground, in the existing East-West fence line.

Set a steel fence post with a Witness corner sign attached 3.0 feet West of the monument.

New Bearing Objects:

- A 5/8" x 30" iron pin bears N 84° E - 15.2 feet. (Flush with the ground).
- A 5/8" x 30" iron pin bears S 38 1/2° E - 19.3 feet. (Flush with the ground).
- A 5/8" x 30" iron pin bears S 49° W - 22.8 feet. (Flush with the ground).
- A 5/8" x 30" iron pin bears N 42° W - 18.9 feet. (Buried 15 inches in ground).

All iron pins are capped with a 1 1/2" yellow plastic cap marked: "WR WELLS, PLS 1106". Bearing Object signs are wired to each iron pin.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

expires 12/31/94

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)