

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

T 2N, R 32E., W.M.

Corner Code No. R-13


Note: Monument marked as shown below

**History of original corner establishment:**

Corner was originally established by Daniel Chaplin, under Contract No. 107, dated September 21, 1864. Set stone 18" x 10" x 8" for corner.

Corner reset by Zenas F. Moody, under Contract No. 165, dated October 4, 1871. Set stone 20" x 14" x 6" for corner.

Corner was re-monumented by Currin and Noland under Special Contract dated May 4, 1887. Currin and Noland found the "Old Corner" and re-monumented with a 24" x 12" x 10" stone set 16 inches in ground and marked with 2 notches on the South edge and 3 notches on the East edge, with a mound of earth raised around the corner and pits dug.



Corner No.  
Compass Declination: 18.0°

**Description of corner evidence found:**

A 18 1/2" x 12" x 8" stone, with notches, lying on top of the ground (as if displaced), about 3 feet East of an old fence corner. The position of the fence corner was also tied to the found corners North, South, East and West. The fence corner intersection was accepted as the best remaining evidence of the original corner location.

Fences extend East-West and South from the corner.

**Description of monument and accessories established to perpetuate the original location of this corner:**

Set 2 1/2" brass cap on 1 1/4" x 30" galv. iron pipe, 28" in ground, original stone buried in earth mound North of new monument.

Set steel fence post 3.2 feet East, with Witness corner sign attached.

**New Bearing Objects:**

- A 5/8" x 30" iron pin bears N 36° W - 27.6 feet.
- A 5/8" x 30" iron pin bears N 85° E - 29.6 feet.
- A 5/8" x 30" iron pin bears S 02° E - 32.1 feet.
- A 5/8" x 30" iron pin bears S 87° W - 35.0 feet.

All iron pins are capped with a 1 1/2" yellow plastic cap, marked " WR WELLS, PLS 1106". Bearing Object signs are wired to each pin.

|   |
|---|
| REGISTERED<br>PROFESSIONAL<br>LAND SURVEYOR |
|---|

*William R. Wells*

|   |
|---|
| OREGON<br>JULY 22, 1977<br>WILLIAM R. WELLS<br>1106 |
|---|

*expires 12/31/94*

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)