

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T 2N, R 32E., W.M.

Corner Code No. R-3

Note: Monument marked as shown below

History of original corner establishment:

The corner was originally established by Daniel Chaplin, under Contract No. 107, dated September 21, 1864. Set post and charred stake in mound of earth, with pits & etc., as per instructions.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

No evidence found. Corner re-established by single proportion measurement between the Southwest and Southeast corners of Section 19.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" x 30" galv. iron pipe, 30 inches in ground, on East side of railroad grade.

Set a steel fence post 3.0 feet North and attached a Witness corner sign.

New Bearing Objects:

- A 5/8" x 30" iron pin bears N 55° E - 36.6 feet. (Flush with ground in fence).
- A 5/8" x 30" iron pin bears S 82° E - 81.0 feet. (Flush with ground in fence).
- A 5/8" x 30" iron pin bears S 16° W - 31.7 feet. (Flush with ground in fence).
- A 5/8" x 30" iron pin bears N 79 1/2° W - 78.4 feet. (Flush with ground in fence).

All iron pins are capped with a 1 1/2" yellow plastic cap marked: "WR WELLS, PLS 1106". Bearing Object signs are wired to each iron pin.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by

(COUNTY OFFICIAL)

(DEPUTY)