

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T 2N, R 32E., W.M.

Corner Code No. R-5

Note: Monument marked as shown below

History of original corner establishment:

Corner established by Daniel Chaplin, under Contract No. 107, dated September 21, 1884. A stone 18 x 10 x 6 was set for the corner. This corner was re-established in 1980 as shown on Map No. R-28-B.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

A 2 1/2" brass cap on 2 1/2" galv. iron pipe protruding 6" from a mound of stone, 4.4 feet South and 2.5 feet East of an existing fence corner (rock jack). Monument set in 1980 by Krumbain Engineering Co. as noted on Map No. R-28-B. A 5/8" iron pin with a plastic cap, marked "WR WELLS, PLS 1106" bears S 31° W - 5.0 feet in the North-South fence, set by W.R. Wells in 1990, as noted on Map No. 90 - 60 - B. The iron pin was protruding 16" from a small mound of stone.

Description of monument and accessories established to perpetuate the original location of this corner:

Attached a Witness corner sign to the corner post of the rock jack.

New bearing objects:

- A 5/8" x 30" iron pin bears N 61 1/2° W - 14.2 feet. (Driven flush with ground).
A 5/8" x 30" iron pin bears N 36 1/2° E - 21.4 feet. (Protruding 10" from grd).
A 5/8" x 30" iron pin bears S 61° E - 57.1 feet. (Protruding 6" from ground).

All pins are capped with a 1 1/2" yellow plastic cap marked: "WR WELLS, PLS 1106". Bearing Object signs are wired to each pin.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells (handwritten signature)

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

expires 12/31/94 (handwritten)

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....
..... by ..... (DEPUTY)
(COUNTY OFFICIAL)