

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/14/94

CORNER DESIGNATION: V-13. Northeast corner Section 33, T2N., R32E., W.M..

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. They reset a stone 10 x 9 x 8 ins., 7 inches in the ground. Dug pits 18 x 18 x 12 ins. in each section, 5 1/2 ft. dist. and raised a mound of earth 2 ft. high, 4 1/2 ft. base alongside. The corner was re-established in County Survey No. 66, performed by John Kimbrell in 1894. Kimbrell set a post in old creek bed and drove stakes for witnesses to the corner on bank of creek North-South and East of corner.

MONUMENT AND ACCESSORIES FOUND: Found 2" square bolt, referenced on all recent recorded surveys.

MONUMENT MARKING DETAIL:

|          |      |
|----------|------|
| T2N      | R32E |
| S28      | S27  |
| S33      | S34  |
| 1994     |      |
| PLS 1106 |      |

MONUMENT SET: Set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, buried 38" in the ground, (marked as shown in the monument detail). Cut off bolt and buried alongside monument.

New Accessories:


Set steel fence post 3.0 feet West with witness sign attached.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 27 1/2° E-25.9 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 6° E-17.1 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears S 75 1/2° W-31.1 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 61° W-24.6 feet.  
Set a steel fence post on line behind monument and attached witness sign. Attached bearing object signs to each pin.

LOCATION & COMMENTS: Corner falls at West edge of gravel driveway.

COMPASS DECLINATION: 18° East.  
FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro



PLS 1106-12-31-94