

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/22/94

CORNER DESIGNATION: X-17. East 1/4 corner section 34, T2N., R32E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. At that time Currin and Noland found old corner, reset a stone, 10 X 8 X 6 ins., 6 inches in the ground for 1/4 Sec. corner, marked 1/4 on W. face; dug pits 18 x 18 x 12 ins. N. & S. from stone 5 1/2 ft. distant. Raised a mound of earth 1-1/2 ft. high, 3-1/2 ft. base over it. The corner was re-established by the U.S. Department of Agriculture, during surveys for the McKay National Wildlife Refuge, in 1938, per Umatilla County Survey No. H-251. The corner was re-established by PLS 933, based on survey H-251, in 1980, per Umatilla County Survey No. R-98-C.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on 2 1/2" galvanized iron pipe, set flush with the ground, per Umatilla County Survey No. R-98-C.

MONUMENT MARKING DETAIL:

T2N R32E  
1/4  
34 ↓ 35  
1980  
PLS 933

MONUMENT SET:

Maintained Corner.

New Accessories:

Attached witness sign to railroad tie corner post, near monument.  
A 5/8" x 30" iron pin with yellow plastic cap stamped 'OR PLS 1106-WA PLS 17372' bears N 5° E-12.8 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped 'OR PLS 1106-WA PLS 17372' bears S 6° E-14.1 feet.  
A railroad tie brace post with a bearing washer stamped "PLS 1106", nailed 0.7 feet above ground, bears S 80° W-8.8 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped 'OR PLS 1106-WA PLS 17372' bears N 86° W-15.3 feet.  
All iron pins have steel fence posts set by them with witness sign attached. Attached bearing object tags to iron pins and above brass washer. Attached witness sign to railroad tie above brass washer and bearing object tag.

LOCATION AND COMMENTS: Corner is located at fence corner with fences extending North-South and West.

COMPASS DECLINATION: 18° East  
FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

EXPIRES  
JULY 22, 1997  
WILLIAM R. WELLS  
1105

Wells 12-21-94