

**PUBLIC LAND CORNER CONDITION REPORT**

**UMATILLA COUNTY, DATE: 11/20/01**

**CORNER DESIGNATION: 2N33, C-1, The West 1/4 Corner of Section 6 only.**


**PREVIOUS RENEWALS/ SURVEYS, ETC..:**

Corner was recovered and remonumented in 1917 survey by L.E. Wilkes, on the West Boundary of the Diminished Reservation Boundary. in 1917. The True Corner is a 12" x 10" top dimension basalt stone marked N W COR RES on East face. This stone was established by Currin and Noland under Contract dated May 4th, 1887. Wilkes Witness Corner monument 1 lk (0.66') South of the Corner stone was remonumented per Corner Record No. 88-19-C recorded in the Umatilla County Surveyor's Office.

**MONUMENT AND ACCESSORIES FOUND:**

Found corner stone of record and a 2 1/2" brass cap on iron pipe witness monument buried 20" below ground, marked as shown in Monument Marking Detail. Per record Corner Record, accessories are intact. The corner has 2 accessories.

**MONUMENT MARKING DETAIL:**

WC  
  
T2N  
R32 E | R33E  
| S6  
S1 | -----  
| N W COR  
RESN  
1988  
PLS 1106

**LOCATION & COMMENTS:**

This corner is located in a farmed field.

**STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD83/91, INT. FOOT:**

For True Corner: N = 739759.34 For witness monument 0.66' S. N = 739758.68

E = 8650514.91

E = 8650514.92

**FIRM/AGENCY:** William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

2N33C1

RECEIVED BY  
Umatilla County Surveyor  
Date 12-01  
Rec'd By KF  
No. 01-211-9

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JUL 21, 19  
WILLIAM R. WELLS  
1106

*renews 6-30-02*