

PUBLIC LAND CORNER CONDITION REPORT

UMATILLA COUNTY, DATE: 12/21/01

CORNER DESIGNATION: 2N33E9, The Northeast Corner of Section 8.

PREVIOUS RENEWALS/ SURVEYS, ETC..:

Most recent Umatilla County Surveyors recorded survey: 98-168-B.

MONUMENT AND ACCESSORIES FOUND:

Found a 2 1/2" brass cap with top 16" above ground level in good condition, marked as shown in monument marking detail. There are no accessories.

MONUMENT MARKING DETAIL:

INDIAN ALLOTMENT

T2N R33E

5 | 4

8 | 9

WC 222.80 N

1919

PLS 933

LOCATION & COMMENTS:

Corner is located 2 feet North of a West running fence along river levee road and 2 feet South of South edge of river levee road. Approximately 6 feet West of fence corner and 2 feet West of a rock crib.

STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD83/91, INT. FOOT:

Witness Corner at 222.8' South:

N = 737090.57

E = 8660974.60

True Corner: (Survey No. 98-168-B)

N = 737313.33

E = 8660972.14

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

2N33E9

RECEIVED BY
Umatilla County Surveyors
Date 5-02
Rec'd By KK
No. 02-109-9

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6/30/02