

PUBLIC LAND CORNER CONDITION REPORT

UMATILLA COUNTY, DATE: 12/31/01

CORNER DESIGNATION: 2N33, J-13, the Northeast Corner of Section 16.

PREVIOUS RENEWALS/ SURVEYS, ETC.:

Corner was reestablished per Umatilla County Surveyor's Survey Number 93-053-C and the accompanying Corner Record.

MONUMENT AND ACCESSORIES FOUND:

Found a 2 1/2" brass cap on 1 1/4" galvanized iron pipe with cap set flush with the ground and marked as shown on monument marking detail. Per Corner Record, all accessories are intact. The corner has four accessories.

MONUMENT MARKING DETAIL:

T2N R33E
S 9 | S 10 W.C.
----- 54.0 ft.
S16 | S 15 EAST
1993
PLS 1106

LOCATION & COMMENTS:

Witness corner falls in a fence row on the East side of the Mission Highway.

STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD83/91, INT. FOOT:

For true corner point: N = 732027.36 For witness corner 54.0' East: N = 732029.10
E = 8666385.68 E = 8666439.64

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

\2N33J13

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

RECEIVED BY

Umatilla County Surveyor

Date 2-02

Rec'd By KK

No. 02-47-9