

T 2N, R 33E, W.M.


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Corner Code No. J13
Note: Monument marked as shown below

History of original corner establishment:

Corner was most recently re-monumented by L.E. Wilkes, U.S. Surveyor, during his subdivision of Section 10. This survey was made in 1917 under Group 29 Instructions dated September 5, 1917. Wilkes found a 6 x 4 x 4 inch stone, set by the County Surveyor, and at a point 49 1/2 links East of the corner point Wilkes set a brass capped iron pipe witness corner.

State Highway Map No. 8B-14-2 shows a state plane coordinate for the corner and a state plane coordinate for the East 1/4 of Section 9, 1/2 mile to the North.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

None. The witness corner monument has been destroyed by road construction. Corner position was re-established based on the state plane coordinate reported on State Highway Map No. 8B-14-2.

Description of monument and accessories I established to perpetuate the original location of this corner:

The corner falls in a paved highway. Set a witness corner monument N 89°25'59" E 54.00' from corner point. Witness corner monument is a 2 1/2" brass cap on 1 1/4" by 30" galv. iron pipe set 29" in the ground. Set a steel fence post 2' North of the corner with a Witness Corner sign attached.

New bearing objects for the witness corner monument:

- A 5/8" x 30" iron pin bears N 19° 50' W - 24.84'.
- A brass washer w/nail bears N 42° 21'E - 67.63'. Washer is stamped PLS 1106, and attached to railroad tie corner post of old corral.
- A brass washer w/nail bears S 12° 47'E - 149.05'. Washer stamped PLS 1106, and attached to a power pole.
- A 5/8" x 30" iron pin bears S 22° 13'W - 21.61'.

All pins are capped with a 1 1/2" yellow plastic cap marked "W.R. Wells, PLS 1106". Bearing Object signs are wired to each pin and nailed to the railroad tie and the power pole.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

expires 12-31-94

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

93-53-C