

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 09/09/97

CORNER DESIGNATION: L-11, The Center Quarter Corner of Section 16.

PREVIOUS RENEWALS/SURVEYS ETC.: None found.

MONUMENT MARKING DETAIL:

T2N R33E
C 1. S16
4
1997
PLS 1106

MONUMENT SET:

Set a 1 1/2" aluminum cap on a 5/8" x 30" iron pin, cap marked as shown in Monument Marking Detail.

Accessories:

A 4" white iron pipe bears N 65° E, 18.9 feet, 1.0' above the ground on the Northwest side. This is a plow line reference pipe.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears S 35° E, 28.2 feet.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears S 54° W, 26.5 feet.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears N 70° W, 25.4 feet.

All bearing objects have bearing object signs attached.

White pipe has survey marker sign and bearing object tag attached..

LOCATION AND COMMENTS: Corner is located near "gore" in plowed field lines.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: John Linder, LSIT
Jason Wells

Note: Corner monument and iron pin bearing object monuments are buried 18" below field surface.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

RECEIVED BY
Umatilla County Surveyor
Date 11-97
Rec'd By KK
No. 97-222-C