

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T 2N, R 33E. , .M.

Corner Code No. L-13

Note: Monument marked as shown below

History of original corner establishment:

This corner was last established by C.E. Redfield, U.S. Indian Service Surveyor, during his surveys in the area between 1911 and 1920. Redfield notes the re-established corner to be 0.473 chains South of a fence line extending East.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

None. The corner area has been disturbed by sewerline and road construction.

The corner was re-established by single proportion measurement between the re-established Northwest and Southwest Corners of Section 15, using Redfield's record.

Description of monument and accessories I established to perpetuate the original location of this corner:

The corner point falls in a paved highway. At a point N 89°38'53" E 42.50 feet from the true corner point, I set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe 30" in the ground as a witness corner monument. The witness corner monument is referenced as follows:

- A 5/8" by 30" iron pin bears N 21° 03' 36" E 32.10'.
- A 3/4" brass washer nailed to UECA pole no. 169400 bears N 48° 31' 35" W 102.68'.
- A 3/4" brass washer nailed to UECA pole no. 169401 bears S 18° 51' 33" W 244.38'.
- A 3/4" brass washer nailed to PP&L pole no. 150400 bears S 00° 02' 12" E 129.82'.

Set steel fence post with witness corner sign attached 1.3' East of the witness corner monument.

The 5/8" iron pin is capped with a 1 1/2" yellow plastic cap marked "W.R. Wells, PLS 1106".

Bearing object signs are nailed to each pole near the 3/4" brass washers. A bearing object sign is wired to the 5/8" iron pin.

The 3/4" brass washers are stamped "PLS 1106".

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Expires 12-31-94

Office of..... County of..... State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by ..... (COUNTY OFFICIAL) (DEPUTY)

93-53-C