

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T 2N, R 33E., .M.

Corner Code No. N-13

Note: Monument marked as shown below

History of original corner establishment:

This corner was last recovered or re-established by C.E. Redfield, U.S. Indian Service Surveyor, during his surveys in the area between 1917 and 1920. Redfield's notes indicate a corner was found, but do not specify what the corner monument was.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

None. The corner area has been disturbed by sewerline and road construction.

A 5/8" smooth iron pin was found in a established East-West fence and field line on the East side of the highway. This pin is on the Easterly right-of-way line of the highway. The corner was re-established by proportionate measure East to West between the calculated position of the Northwest Corner of Section 21 (calculated as shown on Map No. 92-16-B), and the re-established location of the Northeast Corner of Section 22. The smooth 5/8" iron pin was used to control the latitude of the re-established corner. From the re-established corner position, the found 5/8" smooth pin bears N 90°00'00" E 42.50'.

Description of monument and accessories I established to perpetuate the original location of this corner:

The corner point falls in a paved highway. At a point N 89°53'14" E 41.00' from the calculated corner point, I set a 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe, 30" in the ground as a witness corner monument. The witness corner monument is witnessed as follows:

Set steel fence post 1.5' East of witness corner monument and attached witness corner sign.

- A 5/8" by 30" iron pin bears N 03°20' E 44.71'.
- A 5/8" by 30" iron pin bears S 03°18' E 42.90'.
- A 5/8" by 30" iron pin bears S 57°55' W 93.37'.
- A 3/4" brass washer nailed to UECA pole no. 169000 bears N 74°45' W 79.78'.

The 3/4" brass washer is stamped "PLS 1106". The 5/8" by 30" iron pins are capped with 1 1/2" yellow plastic caps marked "W.R. Wells, PLS 1106".

Attached bearing object signs to each iron pin and nailed bearing object sign to UECA power pole no. 169000.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

expires 12-31-94

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

93-53-C