

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 09/25/97

CORNER DESIGNATION: P-9, The West Quarter Corner of Section 21.

PREVIOUS RENEWALS/SURVEYS ETC.: None, since survey by C.E. Redfield.

MONUMENT MARKING DETAIL:

T2N R33E
1/4
S20 | S21
1997
PLS 1106

MONUMENT SET: At position determined by survey on the West line of Section 21, at the Westerly projection of a fence and field line extending West several miles, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 6" below surface of County Road No. 1043, cap marked as shown in Monument Marking Detail.

Accessories:

An aluminum nail with a brass washer stamped "PLS 1106" nailed 1 foot above ground on North side of pole #210500, bears N 89° E, 18.9 feet. Bearing object sign attached.

An aluminum nail with a brass washer stamped "PLS 1106" nailed to the North side of wood fence corner post, 4" above ground, bears West, 36.6 feet. Fences extend West and South. Bearing object sign attached.

South side center of U.S. West phone pedestal bears N 86 1/2° W, 40.2 feet.

Base of underground phone warning sign post bears S 28° E, 39.2 feet. Measured to where sign post enters ground.

LOCATION AND COMMENTS: Corner is 5 feet West of East edge of County Road No. 1043.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: William R. Wells, PLS
Ben Weinke

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-98

RECEIVED BY

Umatilla County Surveyor

Date 11-97

Rec'd By KK

No. 97-222-C