

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 09/05/97

CORNER DESIGNATION: R-11, The North Quarter Corner of Section 28.

PREVIOUS RENEWALS/SURVEYS ETC.: None since survey by C.E. Redfield.

MONUMENT MARKING DETAIL:

T2N R33E

1 S21

4 S28

1997

PLS 1106

MONUMENT SET:

Re-established corner point by single proportionate measure between the Northeast and Northwest corners of Section 28, using the C.E. Redfield record.

Set a 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe approximately 2" below surface of asphalt road, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears N 47° E, 36.93 feet.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears S 65° E, 35.45 feet.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" bears S 44° W, 36.55 feet.

A brass washer on Pacific Power and Light pole #214001, 1.5 feet from ground on south side, stamped "PLS 1106, bears N 65° W, 74.25 feet.

All iron pin bearing objects have signs and fence posts nearby with survey marker signs attached.

LOCATION AND COMMENTS: Corner is located in County Road No. 934.


COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: John Linder, LSIT
Jason Wells



William R. Wells



renews 6-30-98

RECEIVED BY

Umatilla County Surveyor

Date 11-97

Rec'd By KK

No. 97-222-C