

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 09/05/97

CORNER DESIGNATION: R-13, The Northeast Corner of Section 28.

PREVIOUS RENEWALS/SURVEYS ETC.: Found "PK" nail, origin unknown, at four way road intersection. See Survey No. 93-953-C.

MONUMENT MARKING DETAIL:

T2N R33E
S21 | S22
S28 | S27
1997
PLS 1106

MONUMENT SET:

At position of found "PK" nail, set a 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe 2" below surface of asphalt road, cap marked as shown in Monument Marking Detail.

Accessories:

A brass washer, stamped "PLS 1106", 1.0' above ground on Northwest side of Pacific Power and Light Pole #220002, bears N 24° E, 73.4 feet.

A brass washer, stamped "PLS 1106", 1.0' above ground on North side of guy pole #270900, bears S 55° E, 47.75 feet.

A stop sign metal post bears S 54° W, 36.2 feet.

A brass washer, stamped "PLS 1106", about 1.0' above ground on East side of Pacific Power and Light pole #219001, bears N 47° W, 40.6 feet.

LOCATION AND COMMENTS: Corner is located in South Market Road at 4-way road intersection.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: John Linder, LST
Jason Wells

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-98

RECEIVED BY

Umatilla County Surveyor

Date 11-97

Rec'd By JK

No. 97-222-C