

PUBLIC LAND CORNER CONDITION REPORT

UMATILLA COUNTY, DATE: 02/20/02

CORNER DESIGNATION: 2N33V9, The Northeast Corner of Section 32.

PREVIOUS RENEWALS/ SURVEYS, ETC.:

Most recent Umatilla County Surveyors recorded corner record: H-184.

MONUMENT AND ACCESSORIES FOUND:

Found a 2 1/2" brass cap 2" below paved road marked as shown in monument marking detail. The witness cap monument North 30.00 feet is destroyed by road construction. Witness cap monument S 45°E, 42.43 feet is leaning slightly East but in good condition. UECA power pole #280001 has a bearing object sign with nail in center referencing corner, no direction, 38.40 feet. Bearing object sign nailed to wood fence post with nail in center stamped: NE - 67.54 feet, JAN 1994, LS 1333. No visible accessory in Northwest quadrant.

MONUMENT MARKING DETAIL:

UMATILLA
COUNTY
SURVEYOR
29 | 28
32 | 33
T2N
R33E
(No visible date)

LOCATION & COMMENTS:

STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD83/91, INT. FOOT:

N = 715982.41
E = 8661394.42

FIRM/AGENCY: William R. Wells
P.O. Box 1696
Pendleton, Oregon 97801

2N33V9

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6/30/02
RECEIVED BY

Umatilla County Surveyor

Date 5-02

Rec'd By KK

No. 02-122-9