

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla      DATE: 4/14/94

CORNER DESIGNATION: Z-25.    S.E. corner Section 36, T2N., R32E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO survey was made by L.E. Wilkes, Cadastral Surveyor, in 1917. Wilkes' record states: Set an iron post, 3 ft. long, 2 ins. diam., 32 ins. in the ground, for cor. of Tps. 1 and 2 N., Rs. 32 and 33 E., with brass cap. Fence cors. bear N 69° 45' E., 45 lks dist; S 32° 30' E., 30 lks dist., S 64° 15' W., 58 lks dist., N 56° W., 63 lks dist. This corner is at the intersection of roads extending E. and W. and N. and S.

MONUMENT AND ACCESSORIES FOUND: Found Wilkes' brass cap monument for the section corner buried 12" below road surface, from which: A 2 1/2" GLO brass cap on 2" galvanized iron pipe bears South 00° 36' West, 40.0', origin unknown.      A 2  
1/2" BIA brass cap on 2" galvanized iron pipe bears North 00° 36' East, 12.0', origin unknown.

**MONUMENT MARKING DETAIL:**

		L		
		T2N		
G	R32E		R33E	O
	S36		S31	
	S1		S6	
		T1N		
		1917		

**MONUMENT SET:**  
Maintained Corner.

New Accessories:  
Power pole No. 369061 with a brass washer stamped "PLS 1106", nailed 5" above ground, bears N 55 1/2° W-60.1 feet.  
A guy pole with a brass washer stamped "PLS 1106", nailed 6" above ground, bears S 36° W-88.8 feet.  
Poles have witness signs attached, and bearing object signs attached.

**LOCATION & COMMENTS:** Corner is located just East of a road intersection with road extending North, South, East and West.

**COMPASS DECLINATION:** 18° East.  
**FIRM/AGENCY:** William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

William R. Wells  
WILLIAM R. WELLS  
1106

renews 12-31-94