

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 2N, R 33E., W.M.


Corner Code No. Z-5

Note: Monument marked as shown below

History of original corner establishment:

The most recent original record, by U.S. Indian Service Surveyor C.E. Redfield, indicates this corner was recovered in 1919 and an iron post witness corner was set 28 feet S.E. of the corner.

Redfield's notes were found in the BIA Realty Section Vault at the Umatilla Agency.



Z-5

Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

None. A road runs across the corner area and the area where the witness corner would fall has been farmed. After a thorough search of the corner area for existing monumentation, the corner point was re-established by single proportion measurement between the recovered S.W. corner of Section 31 and the recovered South 1/4 corner of Section 32, using C.E. Redfield's record. See Survey No. 92-20-B.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" by 30" G.I.P. 30" in ground and flush with the paved road surface, 3.2' South of centerline stripe from which:

- A 5/8" by 30" rebar bears S 84° 30' E - 314.47'.
- A 5/8" by 30" rebar bears S 39° 49' E - 39.07'.
- A 5/8" by 30" rebar bears S 5° 20' E - 271.18'.
- A brass washer bears N 48° W - 38.21'. Washer is stamped "PLS 1106" and is nailed on a PP&L pole with a Bearing Object sign attached.

All rebar reference monuments are capped with a yellow plastic cap marked "W.R. Wells, PLS 1106". Set steel fence posts set by each rebar with Bearing Object signs attached.

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>William R. Wells</i>
OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by (DEPUTY)
 (COUNTY OFFICIAL)

RECEIVED BY
 Umatilla County Surveyor
 Date _____
 Rec'd By *WR*
 No. 92-20-B