

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 08/01/07

CORNER DESIGNATION: 2N34, A23. The North One-Quarter Corner of Section 1.

PREVIOUS RENEWALS/SURVEYS ETC.:

The Corner was established as part of Indian Allotments surveys by C.E. Redfield, circa 1918-1919. Redfields notes do not state what was set for the corner monument.

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in a CRP field, previously farmed.

MONUMENT MARKING DETAIL:

T3N R34E

1/4 S1
T2N R34E
2007
PLS 1106

MONUMENT SET:

Corner was re-established corner by proportionate measure between the recovered Redfield monuments at the East 1/16th Corner of Section 36 and the Southeast Corner of Section 36, using the Redfield record. At the re-established corner point, set a 2 3/8" brass cap on 1 1/4" x 30" galvanized iron pipe to bedrock with cap buried 8" below ground level. Monument marked as shown in monument marking detail.

New accessories:

A Silver Deep-1 magnet buried 18" below ground level bears North 47° East, 20.7 feet.
A Blue Deep-1 magnet buried 18" below ground level bears South 47° East, 32.6 feet.
A Pink Deep-1 magnet buried 18" below ground level bears South 47° West, 28.8 feet.
A Orange Deep-1 magnet buried 18" below ground level bears North 34° West, 31.0 feet.
Buried bearing objects signs with all Deep-1 magnets. Set steel fence post with "witness" sign attached, 2 feet East of corner monument.

LOCATION AND COMMENTS: Corner is located in a CRP field, previously farmed.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 743194.55
E = 8711473.21

FIRM: William R. Wells, PLS

P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

2N34A23

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08