

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla

DATE: 3/4/94

CORNER DESIGNATION: N-3. N 1/4 corner Section 19, T2N., R36E., W.M..

PREVIOUS RENEWALS/SURVEYS, ETC.: The last official survey was made by C. E. Redfield, U.S. Indian Service Surveyor, during Allotment Surveys on Umatilla Indian Reservation between 1917 & 1920. Redfield established the corner position but did not monument it because the corner fell in Meacham Creek. Redfield set brass cap iron pipe witness corners 130 feet West, 120 feet East, and 560 feet South of the corner position, according to field notes found at the Umatilla Agency.

MONUMENT & ACCESSORIES FOUND: None. The corner position falls on the dike constructed after the flood of 1964. The witness corner monuments have been destroyed by flooding and channel rebuilding of Meacham Creek.

MONUMENT MARKING DETAIL:

T2N R36E
S18
1/4-----
S19
1994
PLS 1106

MONUMENT SET: Re-established corner by single proportion measurement, using Redfield record, between the recovered W 1/16th corner common to Secs. 18 & 19 and recovered closing corner monument at the intersection of the Sec. line common to Secs. 18 & 19 and the East boundary of the Umatilla Indian Reservation. Set a 2 1/2" brass cap on a 1 1/4" X 30" galvanized iron pipe, 25" in the ground, with a mound of stone to the cap.

New Accessories:

Set steel fence post with witness sign attached 2.4 feet West of monument.

A 12" ponderosa pine bears N 20 1/2° W, 40.2 feet, scribed: 1/4 S18 BT.

A 12" ponderosa pine bears N 55° E, 40.9 feet, scribed: 1/4 S18 BT.

A 9" ponderosa pine bears S 57° E, 41.5 feet, scribed: 1/4 S19 BT.

A 10" ponderosa pine bears S 08° E, 27.5 feet, scribed: 1/4 S19 BT. Each new bearing tree has a brass washer, stamped: "PLS 1106" nailed to the face of the blaze, and a bearing object sign and witness sign attached. Painted face of blaze and a 6" red band around each tree.

LOCATION AND COMMENTS: Corner falls on the West top edge of the dike at the East edge of Meacham Creek.

COMPASS DECLINATION: 18° East.

FIRM/AGENCY: William R. Wells, PLS

P.O. Box 1696

Pendleton, Oregon 97801

Surveyor's Seal

Party Chief: Robert D. English

Notes: Robert D. English

Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 12-31-94

RECEIVED BY

Umatilla County Surveyor

Date 7-94

Rec'd By KK

No. 94-78-CLB