


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by Herman D. Gradon, US Deputy Surveyor, under Contract Number 452. The Surveyor General's records state:

Set a post 36 x 3 ins 24 ins. in the ground for 1/4 sec cor marked 1/4 on N-face from which
A fir 5 ins. diam. bears N. 48° E. 9 lks. dist. mkd. 1/4 S. BT.
A tamarack 24 ins. diam. bears S.62°W. 17 lks. dist., marked 1/4 S. BT.



The 1/4 section was monumented in 1998, by Kaiser/Griffin/ Seibold, Cadastral Surveyors under Bureau of Land Management Group No. 1844. The field notes state:

Point for the 1/4 sec. cor. of secs. 6 and 31, at proportionate distance; there is no remaining evidence of the original corner.

Set stainless steel post, 28 ins. long, 2-1/2 ins. diam., 24 ins. in the ground, in a collar of stone, with brass cap mkd., from which

A ponderosa pine, 38 ins. diam., bears N.80°E. 30 lks. dist., mkd. 1/4 S31BT
A ponderosa pine, 30 ins. diam., bears S.38°E. 16 lks. dist., mkd. 1/4 S6 BT.

Deposited a magnet in a white plastic case at the base of the stainless steel post

Description of corner evidence found:

Found 3-1/4" BLM brass cap, marked per the diagram, 0.4 feet above the ground.

38" Ponderosa Pine bears N.80°E., 19.8 feet (BLM Bearing Tree)
30" Ponderosa Pine bears S.38°E., 10.6 feet (BLM Bearing Tree)

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 5/8 x 24 inch rebar with 2 inch aluminum cap, bears N.13°E., 20.2 feet stamped WSI/RM 20.2, 2535.
Set 5/8 x 24 inch rebar with 1-1/2 inch aluminum cap, bears S.71°W., 18.9 feet stamped WSI/RM 18.9, 2535.

Reference monuments have an arrow pointing towards the corner. Appropriate signs have been attached to all bearing trees as required by this US Forest Service contract. 20° declination was used. Fieldwork was performed in July and August 2002.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Michael P. LeJeune

OREGON 11/06/02
JAN. 21, 1992
MICHAEL P. LE JEUNE
2535

EXPIRES 12/31/02

Prepared by: White Shield, Inc.
2515 W. Falls Ave.
Kennewick, WA 99336

Michael P. LeJeune,
Oregon PLS. 2535

Office ofCounty Surveyor....., County ofUmatilla.....,State of Oregon, I hereby certify that the within

instrument was filed in this office for record on theday of

David H. L...
(County Official)

by
(Deputy)

RECEIVED BY
20.....
Umatilla County Surveyor
Date 11-02
Rec'd By KK
No. 12-273-B