


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C - 17

History of original corner establishment:

This corner originally established in 1901 by Charles L. Campbell under his contract number 733:

Set a basalt stone 20 x 10 x 4 inches, 15 inches into the ground marked 1/4 on the west face. Raise mound of stone 3 foot base, 2 feet high, west of corner.



Description of corner evidence found:

Found basalt stone 18 x 12 x 4 inches set in a mound of stones which is definitely man-made. The stone is spalled on the side where marks would have been.

Description of monument and accessories established to perpetuate the original location of this corner:

In place of the original stone, set a 2 1/2 inch by 30 inch aluminum pipe with a 2 1/2 inch aluminum cap attached, marked as shown in the diagram above. The pipe is set into the ground 14 inches to bedrock. Built a mound of stones around the pipe. The original stone is buried along the west side of the pipe. From which:

A 6 inch Ponderosa Pine bears N 77° W, 102.5 feet, scribed "1/4 S3 BT" on double blazes. A 3/4 inch washer, marked "PLS 1636", is nailed flush to the lower blaze and a sign 54-3, Bearing Tree, is nailed above the blazes and a sign 54-9, Land Survey Monument, is nailed to the back.

A 5/8 inch by 36 inch iron rod driven 28 inches into the ground with a 1 1/2 inch aluminum cap attached and marked "USDA-FS RM S2 LS 1636" and an arrow pointing to the corner monument, bears N 54° 30' E, 51.9 feet.

A 5/8 inch by 36 inch iron rod driven 28 inches into the ground with a 5/8 inch brass washer, marked "PLS 1636", wired to the rod at ground level, bears S 44° E, 57.0 feet.

A rock outcrop, 18 inches by 36 inches by 12 inches above the ground, marked "X B0" on the west face, bears S 47° W, 117.5 feet to the "X".

I hereby certify the above corner was perpetuated as hereon described on November 3, 1992. Witness: David Schlaich and Thomas Bradshaw. De: 18° E.

Office of COUNTY SURVEYOR County of UMATILLA  
State of OREGON, I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

REGISTERED PROFESSIONAL LAND SURVEYOR

*Dennis L. Gaylord*

OREGON  
JULY 14 1978  
DENNIS L. GAYLORD  
1636

EXPIRES 12/31/93

RECEIVED BY

Umatilla County Surveyor

Date 12-9-92

Rec'd by AK

No. 92-142-R