

Index  
File No. E-13

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_  
Cor. No. \_\_\_\_\_

T 2N R. 37E


R.D. WALLA WALLA County UMATILLA

Merid. WILL

N.F. UMATILLA State OREGON

CORNER DIAGRAM

T2N R37E



DESCRIBE CORNER MONUMENT FOUND

STONE OF RECORD SIZE MARKED W/ 3 OBLONG HOLES ON NARROW FACE & 5 NOTCHES ON ONE EDGE. SOME OF THE STONE HAS SPALLED OFF ON THIS EDGE. MARKS NEAR TOP. STONE HAS SLD 10' SOUTH.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

ORIG. 24" FIR IS LIVE W/ SINGLE HEALED BLAZE. NOW ABOUT 32". BLAZE IS LOW ON TREE. BEARS S 40° W, 58.1 ft.  
ORIG. 18" PINE IS LIVE W/ SINGLE HEALED BLAZE. NOW 36". BLAZE IS LOW ON TREE. BEARS N 79° W, 90 ft ±

RECORD 94.4 ft. ORIG. 12" PINE IS GONE.

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

THERE IS A PINE ABOUT 150 ft. IN GENERAL DIRECTION OF THE RECORD SE BT WITH A SCAR. THIS MAY BE THE ORIGINAL SE BT BUT RECORD IS INCORRECT. I PUT A LOCATION POSTER ON 4" FIR ON NORTH SIDE OF ROAD 32, 700' SOUTH.

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_  
Signature \_\_\_\_\_

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_  
Agency \_\_\_\_\_

Signature

Title

Division

Headquarters

Date

FS-7100-52 (3/68)

*Dennis L. Hayward*

PLS 1636

11-15-89

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

9

**ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

10

Work Done By \_\_\_\_\_ Title \_\_\_\_\_ Date \_\_\_\_\_ State Registration No. or Agency \_\_\_\_\_

Certified Cor. Record Prepared ? Yes No Filed At: \_\_\_\_\_ Date \_\_\_\_\_

11

**REMARKS**

12

Index File No. T. R. M. Tract or Surv. No. Cor. 13