

USDA-FOREST SERVICE


Index File No. WB 980
 T 2N R. 37E
 Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. WALLA WALLA County UMATILLA Tract or Survey No. _____ Cor. No. _____
 N.F. UMATILLA State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND
 Corner not previously established.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND
 No accessories previously established.

PHOTO IDENTIFICATION DATA
 Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
 Corner falls in shallow draw on rocky, sparsely timbered South slope approximately 850 feet South of the 3150-215 road.

PLANE COORDINATE POSITION DATA
 State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
Agent

Signature

Title SURVEYOR Division _____ Headquarters _____ Date 9-6-91 FS-7100-52 (3/68)

2

3

4

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2½"x30" aluminum pipe with aluminum cap marked as shown:
Pipe is set 30 inches in the ground.

ELEV 4600

WB 980

1991
OPLS 644

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New BTs:

A 9 inch diam. Ponderosa Pine bears N21°E, 50.80 feet marked WB 980 BT
A 14 inch diam. Ponderosa Pine bears S84°W, 61.31 feet marked WB 980 BT

Attached Bearing Tree and Land Survey Monument signs to the BTs
Set a steel fencepost approximately 3 feet Easterly with
Land Survey Monument and Wilderness Boundary signs attached.

10

Work Done By D.I. Griffith Title Surveyor Date 7-08-91 State Registration No. OPLS 644
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: Umatilla Co. Surveyor Off. Date 10-91

11

REMARKS

Witnesses: Jeff Petersen, Jim Bennett and John Osterman

12

Index File No. WB 980 T.2N

R.37E

W.M.

Tract or Surv. No.

Cor.

13