


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:
Corner not previously established.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Corner not previously established.

Description of monument and accessories established to perpetuate the

original location of this corner: At a point on the Wilderness Boundary line at an Elevation of 4600 feet, I set a 2½" x 30" aluminum pipe with aluminum cap marked as shown, 28 inches in the ground, from which:

New Bearing Trees;


- A 16 inch diameter Ponderosa Pine bears N32°E, 91.22 feet marked WB 956 BT
- A 18 inch diameter Douglas Fir bears S86°E, 50.15 feet marked WB 956 BT

Attached Bearing Tree and Land Survey Monument signs to the bearing trees.

Set a steel fencepost approximately 5 feet Westerly with Land Survey Monument and Wilderness Boundary signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on July 3, 1991.

Witnesses: Jeff Petersen, Jim Bennett and John Osterman



**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

[Signature]
 OREGON
 JULY 10, 1964
DUANE I. GRIFFITH
 644

I used a steel tape and magnetic compass in the establishment of new accessories. I used 20° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 10-92
 Rec'd By RR
 No. 92-19-R

WB 956