


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A - 11
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin, deputy, (compassman) on October 24, 1871, under joint GLO contract No. 154, as follows:

Set a stone, 20" x 6" x 5", on southeast hillside for 1/4 section corner to sections 4 and 33, T. 1 & 2 S., R. 30 E.



Original corner evidence recovered:

Found the original corner stone solidly set but tipped to the southeast. The corner stone is 20" x 9" x 6" and is marked "1/4" on the north face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 16" into the ground to bedrock. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone alongside the northwest side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N17° E, 87.8 feet.

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S30° E, 46.5 feet.

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S47° W, 88.8 feet.

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N44° W, 98.5 feet.

I nail a "witness post" sign to a wooden fence post N30° E, 18 feet from the corner.

I hereby certify this corner point was perpetuated as hereon described on February 22, 2003.

Magnetic declination set in compass: 16° E.

NAD '83 UTM Zone 11 position: 5032775N 336214E (plus or minus two meters)



Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
 Umatilla County Surveyor
 Date 5-03
 Rec'd By RK
 No. 03-68-12