

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A - 17
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin, deputy, (compassman) on October 24, 1871, under joint GLO contract No. 154, as follows:

Set a stone, 24" x 6" x 5", on east side of ravine for section corner to sections 2, 3, 34 and 35, T. 1 & 2 S., R. 30 E.

T1S R30E
S34|S35
S3|S2
T2S
PLS 1636
2002

Original corner evidence recovered:

Found the original corner stone loosely set (tipped to the west) in a mound of stones. The corner stone is 24" x 8" x 5" and is plainly marked with two notches on the east edge.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 24" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone alongside the east side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 36" iron rod set 32" into the ground with a 3/4" brass washer, marked "PLS 1636 35", attached at ground level, bears N46° 30' E, 86.6 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S2", attached at ground level, bears S38° E, 87.6 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S3", attached at ground level, bears S24° W, 72.0 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 34", attached at ground level, bears N32° W, 91.4 feet.

I nail a "witness post" sign to a wooden fence post at the corner.

I hereby certify this corner point was perpetuated as hereon described on January 30, 2002. Magnetic declination set in compass: 19° 30' E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Dennis L. Gaylord
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: _____

RECEIVED BY
Umatilla County Surveyor
Date 2-02
Rec'd By KR
No. 02-28-R