


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 7
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 11, 1878, under GLO contract No. 293, as follows:

Set a stone, 17" x 10" x 8", for the 1/4 section corner to sections 5 and 8.



Original corner evidence recovered:

Found the original corner stone solidly set 11" into the ground on the north edge of a mound of stones. The corner stone is 17" x 9" x 8" and is plainly marked "1/4" on the north face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 18" flared, galvanized iron pipe 15" into the ground to bedrock. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 18" iron rod set 16" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N33° E, 87.3 feet.
- A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S56° 30' E, 65.0 feet.
- A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S44° 30' W, 63.8 feet.
- A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N43° W, 63.8 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 11, 2004. Magnetic declination set in compass: 17° E.
NAD '83 UTM Zone 11 position: 5031202N, 334581E (plus or minus two meters).

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 11, 1973
DENNIS L. GAYLORD
1636

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on

RECEIVED BY
Umatilla County Surveyor.
Date 2-04
Rec'd By KK
No. 04-36-R