


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G - 25
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin, on September 7, 1871, under GLO contract No. 154, as follows:

Set a stone, 28" x 10" x 5", for 1/4 section corner.



Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 28" x 12" x 6" and is plainly marked "1/4" on one face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 24" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the southwest side of the pipe and build a mound of stones around the pipe, from which:

- A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N41° 30' E, 84.2 feet.
 - A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S36° 30' E, 107.1 feet.
 - A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S52° W, 100.2 feet.
 - A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N66° W, 83.7 feet.
- This corner marks a point on the Morrow - Umatilla County line.

I hereby certify the above corner point was perpetuated as hereon described on January 28, 2005. Magnetic declination set in compass: 16° E.
NAD '83 UTM Zone 11 position: 5030446N, 332064E (plus or minus two meters).

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY
 Umatilla County Surveyor
 Date 2-05
 Rec'd by KK
 No. 05-021-R
g-2