


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 19
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 4, 1878, under GLO contract Number 293, as follows:

Set a stone, 20" x 14" x 10", on a southwest hillside for the 1/4 section corner for sections 11 and 14.



Original corner evidence recovered:

Found the original corner stone solidly set on the southeast edge of a mound of stones. The corner stone is 19" x 13" x 12" and is plainly marked "1/4" on the north face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe, 16" into the ground to bedrock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I place the corner stone, with the marked face on the ground, along the south side of the pipe, and build a mound of stones around the corner stone and pipe, from which:

A 5/8" x 24" iron rod, set 12" into the ground in a mound of stones, with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N40°E, 72.9 feet.

A 5/8" x 24" iron rod, set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S57°E, 111.4 feet.

A 5/8" x 24" iron rod, set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S38° 30'W, 76.1 feet.

A 5/8" x 24" iron rod, set 20" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N50°W, 86.4 feet to the top of the rod, which is leaning westerly.

A 5 foot steel fence post with a "Witness Post" sign attached bears South, 1.0 foot.

I hereby certify the above corner point was perpetuated as hereon described on June 11, 2000. Magnetic declination set in compass: 18°E.



Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on

RECEIVED BY

Umatilla County Surveyor

Date 6-2000

W'd by KH

No. 00-126-R