


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 5
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 10, 1878, under GLO contract No. 293, as follows:

Set a stone, 18" x 10" x 8", for corner to sections 17, 18, 19 and 20. Dug pits and drove a willow stake as per instructions



Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 23" x 12" x 7" and is plainly marked with five notches on one (east) edge and three notches on another (north) edge. The stake and pits of record are gone.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 16" into the ground. A 2 1/2" brass cap attached to the iron pipe is marked as shown in the diagram above. I bury the corner stone along the northwest side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 18" iron rod set 16" into the ground with a 3/4" brass washer, marked "PLS 1636 17", attached at ground level, bears N49° E, 108.1 feet.

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 20", attached at ground level, bears S19° E, 63.3 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 19", attached at ground level, bears S55° 30' W, 114.7 feet.

A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 18", attached at ground level, bears N31°30' W, 68.4 feet.

I nail a "witness post" sign to a wooden fence post one foot south of the corner.

I hereby certify the above corner point was perpetuated as hereon described on February 25, 2002. Magnetic declination set in compass: 16° E.

REGISTERED PROFESSIONAL LAND SURVEYOR
Dennis L. Gaylord
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 6-02
Rec'd By KK
No. 02-148-R