


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R - 21
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 3, 1878, under GLO contract No. 293, as follows:

Set a stone, 15" x 8" x 5", on a north descent for the corner to sections 23, 24, 25 and 26. Drove a pine stake.



Original corner evidence recovered:

Found the original corner stone loosely set on the northeast edge of a mound of stones. The corner stone is 17" x 9" x 8" and is plainly marked with 4 notches on the north edge and one notch on the east edge. The original pine stake is gone.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" galvanized iron pipe 18" into the ground to bedrock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the north side of the pipe and build a mound of stones around the pipe to the cap, from which:


A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N47°E, 116.6 feet.

A 5/8" x 24" iron rod, set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S51°E, 142.6 feet.

A 5/8" x 36" iron rod, set 34" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S46° 15'W, 114.7 feet.

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NW" attached at ground level, bears N42°W, 78.3 feet.

I hereby certify the above corner point was perpetuated as hereon described on October 5, 2000. Magnetic declination set in compass: 18°E.


Dennis L. Gaylord

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: 10/17/2000

David H. Kline

RECEIVED BY
 Umatilla County Surveyor
 Date 10-20
 Rec'd By KR
 No. 00-217-R