

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R - 9
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 7, 1878, under GLO contract No. 293, as follows:

Set a stone, 17" x 8" x 6", for corner to sections 20, 21, 28 and 29. Dug pits and drove a willow stake as per instructions



Original corner evidence recovered:

Found the original corner stone solidly set on the north edge of a mound of stones. The corner stone is 16" x 9" x 6" and is plainly marked with four notches on the north edge and four notches on the east edge. The stake and pits of record are gone.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 16" into the ground to bedrock. A 2 1/2" brass cap attached to the iron pipe is marked as shown in the diagram above. I bury the corner stone along the southeast side of the pipe and build a mound of stones around the pipe, from which:

- A 5/8" x 18" iron rod set 15" into the ground with a 3/4" brass washer, marked "PLS 1636 21", attached at ground level, bears N60° E, 59.1 feet.
- A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 28", attached at ground level, bears S67° 30' E, 33.6 feet.
- A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 29", attached at ground level, bears S35° W, 60.7 feet.
- A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 20", attached at ground level, bears N41° W, 47.8 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 6, 2002. Magnetic declination set in compass: 17° E.


 REGISTERED PROFESSIONAL LAND SURVEYOR
 OREGON
 JULY 14, 1978
 DENNIS L. GAYLORD
 1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
 Umatilla County Surveyor
 Date 2-02
 Rec'd By KK
 No. 02-33-R