


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L - 25
DIAGRAM

History of original corner establishment:

The original corner was established on October 21, 1871, by George S. Pershin and George Williams under their joint GLO contract No.154, as follows:



Set stone, 16" x 8" x 6" for the 1/4 section corner.

Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 18" x 12" x 10" and is plainly marked "1/4" on one face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 22" into the ground to bed rock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone to the south of the pipe and build a mound of stones around the pipe, from which:

- A 5/8 x 36" iron rod, set 35" into the ground with a 3/4" brass washer attached at ground level, marked "PLS 1636 NE", bears N32°E, 119.8 Feet.
- A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer attached at ground level, marked "PLS 1636 SE", bears S13° 30'E, 187.0 feet.
- A 5/8" x 24" iron rod, set 22" into the ground with a 3/4" brass washer attached at ground level, marked "PLS 1636 SW", bears S78°W, 154.5 feet.
- A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer attached at ground level, marked "PLS 1636 NW", bears N36°W, 69.6 feet.
- A 5 foot steel fence post with a "Witness Post" sign attached bears South, 1.0 foot.

I hereby certify the above corner point was perpetuated as hereon described on June 11, 2000. Magnetic declination set in compass: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 6-2000
Rec'd by KK
No. 00-129-R