

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 21  
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on December 27, 1878, under GLO contract No. 313, as follows:

T2S  
R30 1/2 E  
S14|S13  
S23|S24  
PLS 1636  
1998

Set a stone 17" x 14" x 4" for the corner to sections 13, 14, 23 & 24. Drove a stake in a pit southeast of the corner and raised a mound of stones in lieu of pits.

Corner evidence recovered:

Found the original corner stone loosely set in a mound of stones at a fence corner. Fences project east and north from the corner point. The corner stone is 20" x 15" x 5" and is plainly marked with 3 notches on one edge. The original stake is gone, as is the pit called in the original notes.

Monument and accessories established to perpetuate the original position of this corner:

At the southwest edge of the mound of stones, I set a 1" x 30" iron pipe 7" into bedrock. I place the corner stone along the south side of the pipe and build a mound of stones around the pipe to the cap. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N55°30'E, 128.7 feet.

A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S65°E, 170.2 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S58°W, 106.6 feet.

A 5/8" x 24" iron rod set 15" into the ground and surrounded by a mound of stones, with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N33°15'W, 97.7 feet.

I hereby certify the above corner point was perpetuated as hereon described on September 23, 1998. Magnetic declination: 18°E.



Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on December 31, 1998.

RECEIVED BY  
Umatilla County Surveyor  
Date 12-98  
Rec'd By KK  
No. 98-2532