

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P - 21
DIAGRAM

History of original corner establishment:

The original corner was established on December 27, 1878, by George S. Pershin under his GLO contract No. 313, as follows:

Set stone, 18" x 14" x 5", on east hillside in a mound of stones for 1/4 section corner.

T2S R30 1/2E
1/4
S23|S24
PLS 1636
2000

Original corner evidence recovered:

Found original corner stone loosely set in a mound of stones. The corner stone is 20" x 14" x 5" and is plainly marked "1/4" on one face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" galvanized iron pipe 16" into the ground to bedrock. A 2 1/2" brass cap attached to the iron pipe is marked as shown in the diagram above. I bury the original corner stone along the west side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod, set 21" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N64° 45'E, 89.5 feet.

A 5/8" x 24" iron rod, set 18" into the ground in a small mound of stones, with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S25°E, 160.4 feet.

A 5/8" x 24" iron rod, set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S48° 45'W, 133.1 feet.

A 5/8" x 24" iron rod, set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N37°W, 124.5 feet.

I nailed a "Witness Post" sign to a wood fence post adjacent to the east edge of the corner monument.

I hereby certify the above corner point was perpetuated as hereon described on October 13, 2000. Magnetic declination set in compass: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Dennis L. Gaylord
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: 10/17/2000

David H. Klein

RECEIVED BY
Umatilla County Surveyor
Date 10-00
Rec'd By RK
No. 00-215-R