


History of original corner establishment:

The original corner was established by Daniel Chaplin on November 20, 1864, under GLO contract No. 107, as follows:

Set a stone, 16" x 12" x 12", for the 1/4 section corner.



Description of corner evidence found:

Found a rough surfaced stone, with faint chisel marks visible, in a mound of stones. The corner stone is 16" x 12" x 11".

Description of monument and accessories I established to perpetuate the original location of this corner:

Moving the corner stone aside, I set in it's place a 1 1/2" x 30" iron pipe 28" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram. I bury the corner stone along the northeast side of the pipe and build a mound of stones around the cap, from which:

- A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S10 NE", attached at ground level, bears N36°30'E, 146.0 feet.
- A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S15 SE", attached at ground level, bears S31°30'E, 124.9 feet.
- A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S15 SW", attached at ground level, bears S56°W, 111.4 feet.
- A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S10 NW", attached at ground level, bears N37°W, 142.4 feet.

I hereby certify the above corner point was perpetuated as hereon described on May 12, 1997. Magnetic declination: 20° E.
Witness: Milena Gaylord.

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON
JULY 12 1997
DENNIS L. GAYLORD
1636

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office for record on the 12 day of May, 1997
David H. K. (COUNTY OFFICIAL) by..... (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date 5-97
Rec'd By KK
No. 97-101-R