


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L - 17

History of original corner establishment:

The original corner was established by Daniel Chaplin on November 19, 1864, under GLO contract No. 107, as follows:

Set a stone, 20" x 8" x 6", for the 1/4 section corner.



Description of corner evidence found:

Found the corner stone plainly marked "1/4". The stone is lying loose on the southerly edge of a mound of stones, and is 20" x 12" x 4".

Description of monument and accessories I established to perpetuate the original location of this corner:

In place of the stone, I set a 1 1/2" x 30" iron pipe 17" into the ground to bedrock. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the north side of the pipe monument and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 24" iron rod, set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 S14 NE", attached at ground level, bears N40°E, 90.2 feet.

A 5/8" x 24" iron rod, set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 S14 SE", attached at ground level, bears S39°E, 81.2 feet.

A 5/8" x 24" iron rod, set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 S15 SW", attached at ground level, bears S37°W, 130.1 feet.

A 5/8" x 24" iron rod, set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 S15 NW", attached at ground level, bears N47°30'W, 95.9 feet.

I hereby certify the above corner point was perpetuated as hereon described on April 28, 1997. Magnetic declination: 20°E.
Witness: Milena Gaylord



Office of _____ County of _____
 State of _____, I hereby certify that the within instrument was filed in this office
 for record on the 29 day of April, 1997.
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 4-97
 Rec'd by RR
 No. 97-84-R

GPO-791-311