


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 11
DIAGRAM

History of original corner establishment:

The original corner was established by Daniel Chaplin on November 21, 1864, under GLO contract No. 107, as follows:

Set stone 20" x 6" x 6" for 1/4 section corner.



Corner evidence recovered:

Found the original corner stone solidly set in a large mound of stones. The corner stone is 16" x 7" x 5" and is plainly marked "1/4" on the east face.

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe, 16" into the ground to bedrock. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the south side of the iron pipe and build a mound of stones around the pipe to the cap, from which:

- A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level bears N54°E, 120.0 feet.
- A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level bears S40°30'E, 99.0 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level bears S57°30'W, 108.8 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level bears N36°30'W, 97.5 feet.

I hereby certify the above corner point was perpetuated as hereon described on April 16, 1998. Magnetic declination: 18°E.


Dennis L. Gaylord


Renews June 30, 1999.

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
 Umatilla County Surveyor
 Date 4-98
 Rec'd By AK
 No. 98-166-R