

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 21
DIAGRAM

History of original corner establishment:

The original corner was established by Daniel Chaplin on November 18, 1864, under GLO contract No. 107, as follows:

Set a stone 18" x 12" x 5" for corner to sections 13, 14, 23 & 24.

T2S R31E
S14|S13
S23|S24
PLS 1636
1998

Corner evidence recovered:

The original corner stone is loosely set in a small mound of stones. The stone is 17" x 11" x 5" and is plainly marked with one notch on one edge and one notch on the opposite edge.

Monument and accessories established to perpetuate the original location of this corner:

At the point occupied by the original corner stone, I set a 1" x 30" iron pipe, 23" into the ground. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe to the cap. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level bears N56° E, 136.8 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level bears S31° E, 109.3 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level bears S48° W, 131.3 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level bears N28° W, 119.4 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 26, 1998. Magnetic declination: 18° E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylord

OREGON
JULY 14 1978
DENNIS L. GAYLORD
1636

Renews 6/30/1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY

Umatilla County Surveyor
Date 4-98
Rec'd By RR
No. 98-47-R